

TECHNICAL NOTE **WORK REQUEST NO: 17395**

Install current monitoring instrumentation for SR bakeout skids in sectors 13/14 & 15/16

Engineer: R. Dortwegt

Chief Technician: R. Ferry (work supervisor)

Radiation Safety System: no

Red tag: no

When performing this work:

1. ME personnel will LOTO the bakeout skids per Revision 5 of procedure 310303-00092.
2. Vacuum Group personnel will perform LOTO over ME Group locks per Revision 5 of procedure 310303-00092.
3. ME Group technicians will cut hole in panel door with template made by R. Wright and tested on the bakeout skid in Sector 36. The panel display will then be mounted.
4. Vacuum Group personnel will install electronics and wiring in the skid under the supervision of J. Gagliano.
5. ME Group personnel will use a 1000V megger to hi-pot the new installation. Detailed instructions will be provided when this procedure is to be done.