

Stanford Linear Accelerator Center



SLAC EPICS Projects

Yesteryear, Today, and Tomorrow



Present ESD EPICS

- PEP-II RF – 8 VXI-based stations
- Bunch Injection
- Damping Ring RF – Allen Bradley support

- Bucket-wise luminosity monitor
- NLC Test Accelerator – 2 VME IOCs
 - 60/120 Hz pulsed operation
- PEP-II Tune tracker

- Other SLAC EPICS Projects
 - Longitudinal Feedback – John Fox's group
 - SPEAR III upgrade (Ongoing)
 - BaBar – Slow control – many IOCs.




EPICS Tools and Applications

- StripTool is now a sine qua non of the control room
- Channel Archiver being mated to Oracle for speed and flexibility
- VDCT (newest Database Configuration Tool) now treated as a reliable tool.
- EDM (newest Display Manager) now available at SLAC for test
- Alarm Handler in use
- Strong core of EPICS developers, growing as we speak.



Fill and luminosity data






NLC Test Acc. Upgrade

- Veetest & Labview (1/2 Hertz)
- EPICS replacement
 - Two new IOCS
 - 60 Hz RF control
 - Scanning ADC fault data
 - Complex subroutine records



PEP-II Tune Tracker





ESD EPICS Devices

- Allen Bradley – DCM-based
- GPIB – ethernet LAN and Industry Pack
- Shared Memory – Bit3
- Many SLAC-specific RF VXI-based modules
- CAMAC hardware and drivers from TJNAF
- VSAM (Slow analog)– BaBar and NLCTA
- ADC, TDC, DAC, Dig. I/O – NLC Test Accelerator



Current ESD Epics Projects

- **NLC 8-Pack Support (Due end of Autumn)**
 - Next Step for the NLC Test Accelerator
 - New ADCs, RF Control
- **General GPIB support (Wishlist)**
 - Replacing HPUX-based GPIB support
- **PEP-II RF upgrade (Due end of Summer)**
 - More RF stations, enhanced VXI RF modules



Current EPICS Plans

- Upgrade PEP-II RF IOCs from niCpu030 to PPC VXI Controllers
- Move all production to 3.13.6 during the summer
- Provide SNL/SEQ support
- Continue to coordinate SLAC-wide EPICS
- Look seriously at RTEMS
- Switch to VDCT
- Keep abreast of 3.14 readiness
- Provide SLAC EPICS training




Linear Coherent Light Source

- Just passed CD-1 Lehman review
- SLAC/LLBL/LLNL/Argonne collaboration
- 270 Million dollar project
- Construction start 2006/ready 2008
 - When do we get first real money?
- EPICS to be used wherever reasonable




The LCLS (Linac Coherent Light Source)



10-97
8360A1




LCLS Injector Parts



D. Dowell
X2494
March 27, 2002



LCLS Injector in EPICS



MPG
Beam Codes
BGRPS
Etc.


Timing slave to SLC
Timing master for
Klystron IOCs

Evaluate APS / SNS
timing systems

All Klystrons either
fully SLC or fully
EPICS!



LCLS Site Plan





LCLS Undulator Controls

- Supplied by Argonne APS - lock, stock, and barrel
 - Employs and extends designs from LEUTL (Low Energy Undulator Test Line)
 - All EPICS, 16 VME IOCs
- Argonne and SLAC EPICS groups will coordinate efforts during the whole project
 - Timing
 - Machine Protection
 - Networking
 - Global Feedbacks
 - EPICS Details
 - VME Crates, CPU types
 - Naming Convention
 - Database and screen design
 - Commissioning and integration